

Hollywood Road Consolidated Drain #524

NOTICE OF LETTING OF DRAIN CONTRACT AND DAY OF REVIEW OF APPORTIONMENTS

IMPORTANT NOTICE

NOTICE IS HEREBY GIVEN TO PROPERTY OWNERS AND GOVERNMENTAL UNITS APPORTIONED A PERCENTAGE OF THE COSTS OF THE PROJECT:

Property Owners within the Hollywood Road Consolidated Drain #524 Drainage District, Lincoln Charter Township at Large, Royalton Township at Large, St. Joseph Charter Township at Large, and Berrien County at Large

NOTICE IS GIVEN, that on **Tuesday, March 16, 2010, between 9:00 A.M. and 5:00 P.M. (local time)**, in the **Board of Commissioners Room, Berrien County Administration Center, 701 Main Street, City of St. Joseph**, County of Berrien, State of Michigan, or at any adjourned time and place, a Day of Review of Apportionments will be held to review the apportionment of benefits for the lands within the **"HOLLYWOOD ROAD CONSOLIDATED DRAIN #524."** Any interested person wishing to be heard or wishing to inspect the computation of cost with respect to the special assessments may appear during the day and time specified.

The following is a description of land constituting the Hollywood Road Consolidated Drain #524 Drainage District:

In Lincoln Charter Township, T.5 S.-R.19 W., Berrien County, Michigan; the East 1/2 of the S.E. 1/4 of Section 11; the S.W. 1/4 of Section 12; the N.W. 1/4 of Section 13; the North 150 feet of the East 660 feet of the S.W. 1/4 of Section 13; the East 500 feet of the N.E. 1/4 of Section 14.

In Royalton Township, T.5 S.-R.19 W., Berrien County, Michigan; the S.E. 1/4 of Section 12; the N.E. 1/4 of Section 13; the North 850 feet of the S.E. 1/4 of Section 13.

In Royalton Township, T.5 S.-R.18 W., the West 1/2 of the S.W. 1/4 of Section 7; the South 500 feet of the West 1200 feet of the N.W. 1/4 of Section 7; the West 450 feet of the North 1,000 feet of the South 1,500 feet N.W. 1/4 of Section 7; the N.W. 1/4 of the N.W. 1/4 of Section 18.

In St. Joseph Charter Township, T.5 S.-R.19 W., Berrien County, Michigan; the South 3/4 of the N.E. 1/4 of Section 12; the South 1/2 of the South 1/2 of the N.W. 1/4 of Section 12; the S.E. 1/4 of the N.E. 1/4 of Section 11.

You are further advised that, pursuant to Section 155 of the Michigan Drain Code, any owner of land within the drainage district or any city, township, district or county, feeling aggrieved by the apportionment of benefits made by the Drain Commissioner, may appeal the apportionment within 10 days after the Day of Review of Apportionments by making an application to the Berrien County Probate Court for the appointment of a Board of Review.

INFORMATION FOR CONTRACTORS

A mandatory pre-bid conference will be held at 10:00 a.m. (local time) on Wednesday, February 10, 2010, in the Board of Commissioners Room, Berrien County Administration Center, 701 Main Street, City of St. Joseph. Representatives of the Drain Commissioner and Engineer will be present to discuss the Project. Bidders are required to attend and participate in the conference. Engineer will transmit to all prospective Bidders of record such Addenda as Engineer considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be binding or legally effective.

Prior to **10:00 a.m. (local time) on Tuesday, February 23, 2010, in the Board of Commissioners Room, Berrien County Administration Center, 701 Main Street, City of St. Joseph, I, ROGER H. ZILKE**, Berrien County Drain

Commissioner, State of Michigan, will receive sealed bids, and at **10:00 a.m. (local time)**, bids will be opened and publicly announced for the construction or maintenance of a certain Drain known and designated as **“HOLLYWOOD ROAD CONSOLIDATED DRAIN #524,”** located and established in Lincoln Charter Township, Royalton Township, and St. Joseph Charter Township in the County of Berrien.

IT IS UNDERSTOOD THAT THE FOLLOWING QUANTITIES ARE APPROXIMATE AND THAT FINAL PAYMENT WILL BE MADE ON MEASURED QUANTITIES.

Estimated Quantity	Unit	Description
<u>DIVISION I - HOLLYWOOD ROAD CONSOLIDATED DRAIN #524</u>		
OPEN CHANNEL CONSTRUCTION		
1205	Lin. Ft.	Two-Stage Channel Construction, Detail A
2905	Lin. Ft.	Two-Stage Channel Construction, Detail B
100	Lin. Ft.	Transition Channel Construction
1500	Lin. Ft.	Open Channel Excavation
5180	Lin. Ft.	Spoil Leveling
1180	Lin. Ft.	Spoil Hauling
85	Lin. Ft.	Bank Construction, Sta. 17+75
240	Lin. Ft.	Riffle Construction
210	Lin. Ft.	Pool Construction
DRAIN CROSSINGS		
No. 2 - STATION -1+55 & -0+67 - Interstate 94		
1	Lump Sum	Excavation/Sediment Removal
No. 3 - STATION 1+63, St. Joseph Township - Park Bridge		
1	Lump Sum	Excavation/Sediment Removal
No. 4 - STATION 16+15 - Maiden Lane		
1	Lump Sum	Excavation/Sediment Removal
No. 5 - STATION 25+88 - Lincoln Avenue		
95	Lin. Ft.	10' Span x 8' Rise Concrete Box Culvert, Trench Detail C
100	Lin. Ft.	Guardrail
160	Sq. Yd.	Bituminous Road Restoration (3"- 3C, 2"- 36C)
No. 6 - STATION 30+04, St. Joseph Public Schools - Footbridge		
1	Lump Sum	Remove Existing Structure
1	Lump Sum	Timber Footbridge Construction
No. 7 - STATION 41+01, Cortson, L. & Kiel, K. - Farm Crossing		
50	Lin. Ft.	87" Rise x 63" Rise C.M.P.A. (Polymer Precoated, 3" x 1" Corr., 12 Ga. With Beveled Ends)
No. 8 - STATION 42+38, Cortson, L. & Kiel, K. - Farm Crossing		
1	Lump Sum	Remove Existing Structure
No. 9 - STATION 53+49, Nye, J. - Farm Crossing		
1	Lump Sum	Remove Existing Structure
No. 10 - STATION 59+82 - Michelle Drive		
88	Lin. Ft.	7' Span x 4' Rise Concrete Box Culvert, Trench Detail C
165	Sq. Yds.	Bituminous Road Restoration (3"- 3C, 2"- 36C)
No. 11 - STATION 53+16 - Kristine Street		
88	Lin. Ft.	7' Span x 4' Rise Concrete Box Culvert, Trench Detail C
165	Sq. Yds.	Bituminous Road Restoration (3"- 3C, 2"- 36C)
MISCELLANEOUS		
Multiple	-----	Road Restoration, Several Soil Erosion and Sedimentation Control Measures and Bank Restoration (See Berrien County Drain Commissioner for details).
<u>DIVISION II - GORDON ROAD & MAIDEN LANE BRANCHES</u>		
OPEN CHANNEL CONSTRUCTION		
1272	Lin. Ft.	Open Channel Excavation
1332	Lin. Ft.	Spoil Leveling, Detail C
55	Lin. Ft.	Riffle Construction

25 Lin. Ft. Pool Construction

STORM SEWER CONSTRUCTION

570 Lin. Ft. 66" C 76-III Storm Sewer, Trench Detail A
1280 Lin. Ft. 66" C 76-III Storm Sewer, Trench Detail B
600 Lin. Ft. 15" Storm Sewer, Trench Detail B
3 Each 66" Prefabricated Pipe Radius (7.5°), Sta. 11+26
3 Each 66" x 48" Manhole Tee
2 Each 10' Dia. Storm Sewer Manhole/Catchbasin
1 Each Storm Sewer Lead - 8 Lin. Ft. of 12" C-76-III Storm Sewer, Sta. 5+70
1 Each Storm Sewer Lead - 8 Lin. Ft. of 15" C-76-III Storm Sewer, Sta. 7+57
1 Each Catchbasin Lead - 8 Lin. Ft. of 24" C-76-III Storm Sewer, Sta. 15+80
3 Each Yard Basin Lead - 18 Lin. Ft. of 12" SDR-35 PVC and Inline Check Valve with Cleanout
2 Each Bulkhead Existing Storm Sewer, Sta. 5+70 & 7+57
1 Lump Sum 15' x 10' Junction Chamber, Cast-in-Place With Sanitary Sewer Bridge
1 Lump Sum Inlet Structure With Trash Rack
2 Each 4' Dia. Catchbasin
3 Each 30" Dia. Nyloplast Yard Basin
1800 Sq. Yd. Bituminous Road Restoration (3"- 3C, 2"- 36C)

MAIDEN LANE CROSSING

65 Lin. Ft. 48" C 76-III Storm Sewer, Trench Detail A
1 Each 48" C 76-III R.C.P. Flared End Section
1 Each 36" C 76-III R.C.P. Flared End Section
1 Each 9' Dia. Storm Sewer Manhole/Catchbasin
1 Each 8' Dia. Storm Sewer Manhole/Catchbasin
1 Each 7' Dia. Storm Sewer Manhole/Catchbasin
4 Each Catchbasin Lead - 16 Lin. Ft. of 24" C-76-III Storm Sewer With Flared End Section
900 Sq. Yd. Bituminous Road Restoration (3"- 3C, 2"- 36C)

MISCELLANEOUS

Multiple ----- Road Restoration, Several Soil Erosion and Sedimentation Control Measures and Bank Restoration
(See Berrien County Drain Commissioner for details).

DIVISION III - MILLER AND BEACH BRANCH

OPEN CHANNEL CONSTRUCTION

620 Lin. Ft. Open Channel Excavation
2100 Lin. Ft. Open Channel Cleanout
740 Lin. Ft. Spoil Leveling, Detail C
2100 Lin. Ft. Spoil Leveling, Detail A
70 Lin. Ft. Riffle Construction
50 Lin. Ft. Pool Construction
1 Lump Sum Inline Wier Structure

STORM WATER DETENTION BASINS

1 Lump Sum Inlet Control Structure With Trash Rack and Sluice Gate
1 Lump Sum 6' Dia. Water Level Control Structure
1 Lump Sum Earth Excavation
1 Lump Sum Spoil Leveling
1200 Cu. Yd. Haul and Disposal of Spoils
60 Lin. Ft. 48" C 76-III Storm Sewer, Trench Detail B
469 Lin. Ft. 42" Storm Sewer, Trench Detail B
1 Each 6' Dia. Storm Sewer Manhole/Catchbasin
2140 Lin. Ft. Chain Link Fence
1 Each Post and Chain Gate
1 Lump Sum Viewing Platform

MISCELLANEOUS

Multiple ----- Several Soil Erosion and Sedimentation Control Measures and Bank Restoration (See Berrien
County Drain Commissioner for details).

DIVISION IV - RESTORATION

PLANTINGS - (SUPPLY ONLY)

18980 Each Wetland Plants, Multiple Species and Wetland Type

WETLAND SEEDING

5.2 Acre Wetland Seeding, Multiple Species and Wetland Type

MISCELLANEOUS

Multiple ----- Several Soil Erosion and Sedimentation Control Measures and Bank Restoration (See Berrien County Drain Commissioner for details).

The bidding documents required for review or bidding purposes may be obtained from Roger H. Zilke, the Berrien County Drain Commissioner, 701 Main Street, St. Joseph, Michigan, beginning **February 8, 2010** and are available for a \$50.00 fee.

Payment for the above mentioned work will be made by monthly progress payments on the **third Thursday of each month**.

Any person(s) desiring to bid on the above mentioned work will be required to deposit with the Drain Commissioner a bid bond, certified check, money order or cash in the amount of 5% (five percent) of the bid as a guarantee that he will enter into the contract and furnish the required performance bond and proof of insurance as prescribed by law. The checks of all unsuccessful bidders will be returned after contracts are awarded.

Contracts will be entered into with the lowest responsible bidder giving adequate security for the performance of the work in the sum as specified in the bidding documents. The **Berrien County Drain Commissioner reserves the right to reject any and all bids deemed not in the best interest of the HOLLYWOOD ROAD CONSOLIDATED DRAIN #524 or the County of Berrien** and to adjourn such bid letting to such time and place as he shall publicly announce.

The date for the completion of such contract will be announced at the time and place of letting.

Proceedings conducted at the pre-bid conference, bid opening and day of review are subject to the Michigan Open Meetings Act. Persons with disabilities needing accommodations for effective participation should contact Roger H. Zilke, the Berrien County Drain Commissioner at (269-983-7111) or through the Michigan Relay Center at (800) 649-3777 (TDD) at least fourteen (14) days before each to request mobility, visual, hearing or other assistance.

AND EACH OF YOU, owners and persons interested in the aforesaid lands and public corporations, are cited to appear at the time and place of such bid letting and day of review of apportionments aforesaid, and be heard with respect to such special assessments and your interests in relation thereto, if you so desire.

The review of apportionments is consistent with the Michigan Drain Code of 1956, as amended.

If you have any questions regarding the contract documents, contact: Roger H. Zilke, Berrien County Drain Commissioner (at number listed below) or Larry Protasiewicz, P.E., Spicer Group, Inc., (989) 928-8013.

DATED: February 3, 2010

ROGER H. ZILKE, Berrien County Drain Commissioner
Berrien County Administration Center, 701 Main Street, St. Joseph, MI 49085-1316
(269) 983-7111 Ext. 8261